GOVERNMENT OF WEST BENGAL
Office of the Assistant Engineer
Housing Construction Sub-Division No.-XIV
Asansol

Memo No. 3634 Dated. 27.01.15

ABRIDGED TENDER NOTICE

N. I. T. No. 10 of 2014 -2015 of A. E. / H. C. S. D.-XV

Sealed Tender in printed Form as specified below are invited from the eligible contractors as per particulars given below & will be received by the Assistant Engineer, Housing Construction Sub-Division No-XIV, in the tender Box kept in his office chamber on the date & upto the time specified herein & will be opened by him, in person, on the same day half-an-hour after the time of receipt of tender in presence of such intending tenderers or their Agents as may choose to attend. The Assistant Engineer reserves right to reject any or all the tenders & applications so received without assignment of any reasons thereof.

a)	Name of Work	:	As per list enclosed.
b)	Eligiblityof contractors for issuing tender Form to submit Tender	:	do
c)	Estimated Cost of work put to tender	:	do
d)	Time allotted for completion of work	:	do
f)	Criteria for eligibility	:	Willing contractors will apply for eligibility.In their printed pad containing full mailing address and application must accompany non-refundableXerox copy of following essential documents(Original to be shown for verification by this office) i)PAN card, Vat Registration, Sales Tax Clearance certificate, Professional tax receipts challan,40% credential in a single work of similar nature work of last 3 (three) years from date of publish NIT. ii) Attested Xerox copies of documents invariably signed by the intending tenderers with date to be submitted alongwith the application for the issue of Tender papers.
g)	Earnest Money		As per annexure (To be deposited in the shap of Bank Draft or pay order in any Nationasl Bank of India in favour of the Executive Engineer. Housing Construction Division No. V Durgapur.)
h)	Last date of purmission for puchasing tender papers		: 11.02 .2015 Upto 2.00 p.m.(IST)
i)	Last date & time for receipt of tender in seal cover		: 17.02.2015 Upto 2.00 p.m.(IST)
j)	Date & time of opening tenders		: 17.02.2015 Upto 2.30 p.m.(IST)
k)	Location of Go-down / stack yard from where Deptt. materials will be supplied		: Deptt.Go-down at R.H.E. (polo ground)

l) The undersigned will have to decide eligibility of the contractor on the basic of his submitted papers and reserves the right to refuse any explanation to contractors for eligible after scrutiny.

m) No Arbitration for the work will be admissible as per G.O. No. 3370-A Dated 20.03.1987 (Rules 19 of P.W.Rules 1987)

n) The Accepting Authority reserves the right to reject any or all tender without assigning reason whatsoever.

o) Printed tender forms & other documents W.B.Form 2911/2911(i)/2911(ii) as applicable for all works to be download from relevant website. The successful tenderer will have to execute an agreement in W.B.Form 2911/2911(i)/2911(ii) as applicable along with necessary documents.

Asansol
Assistant Engineer 27/01/15
Housing Constn. Sub-Divn. No.XV

Details Particulars for Notice Inviting Tender no-10 of A.E.H.C.S.D XIV.Asansol

Sl. No.	Description of the Work	Particulars of the work		Time of completion of work	Tenderer Eligible	Schedule of Rates for the year applicable	No of call
		Estimated Amount	Earnest Money				
1	special repair work for construction of Boundary wall in the vacant land & vertical Extension of exist old wall near vacant land in the complex of Kalyanpur Rental Housing Estate in the District of Burdwan	254151	5083	21 days	Bonafide outside agencies having 40% credential in theSingle work of similar nature of last 3 (three) years from date of publish NIT.	PWD(WB) Schedule of rates w.e.f. 01-07-14.	Ist Call
2	special repair work for main drain at Back sides of Kalyanpur Market, Asansol in the district of Burdwan	267035	5341.0	21 days	Bonafide outside agencies having 40% credential in theSingle work of similar nature of last 3 (three) years from date of publish NIT.	PWD(WB) Schedule of rates w.e.f. 01-07-14.	Ist Call

27/01/15

Assistant Engineer
Housing Constn. Sub-Divn.XIV
Asansol

n) The Accenting Authority

Memo no Date

Copy forwarded for information with request to paste a copy of tender notice On notice board for wide publicity.

1. The Executive Engineer ,Housing construction division. No –v
2. The Executive Engineer-I,P.W.D. Asansol
3. The Assistant Engineer,Highway sub divn,Asansol
4. The Assistant Engineer,social sector P.W.Dte,asansol
5. The Assistant Engineer,Housing Construction sub divn no-XV, Durgapur
6. The Assistant Engineer,Housing Construction sub divn no-XIII,Burdwan
7. The Sub- divisional officer,information& cultural deptt,Asansol
8. The Secretary,un-employed engineers co operative socity ltd,Burdwan
9. Notice board of this office for information

27/01/15

Assistant Engineer
Housing Construction Sub- Div-XIV
Asansol

name of work-special repair works for main drain at back sides of Kalyanpur market ,asansol in the dist of Burwan

sl no	description of item	unit	Qty	rate	Amount
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (c) Depth of excavation for additional depth beyond 3000 mm. upto 4000mm. excluding cost of shoring as necessary	%m3	82.00	12047.00	9879.00
2	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) (B) Do - by fine sand	%m3	9.00	56872.00	5118.00
3	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	m2	21.00	340.00	7140.00
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (f) 25 mm to 30 mm shuttering without staging in foundation (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	m2 m2	6.600 4.200	221.000 351.000	1459.000 1474.000
5	(I) Cement concrete with graded stone ballast (40 mm size excluding shuttering) In ground floor (A) [Pakur Variety] (a) 1:3:6 proportion	m3	9.00	5363.00	48267.00
6	Brick work with 1st class bricks in cement mortar (1:6) (a) In foundation and plinth	m3	31.500	5155.000	162383.000

7	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour. In ground floor. (iii) 35 mm. thick	m2	39.00	362.00	14118.00
8	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	m3	0.26	6293.8	1636
9	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor / upto 4m (i) Tor steel/Mild Steel	M.T	0.02	68359	1367
10	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] **(ii) With 1:4 cement mortar** (b) 15 mm thick plaster	m2	59.00	164.00	9676.00
11	Neat cement punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc. NOTE : Cement 0.152 cu.m. per 100 sq.m.	m2	55.00	38.00	2090.00
12	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work) (a) With earth obtained from excavation of foundation.	%m3	31.00	7831.00	2428.00
				TOTAL	**267035.00**

(Two lakh sixty seven thousand thirty five only)

27/01/15

Assistant Engineer
Housing Construction Sub-Div-XIV
Asansol

special repair work for construction of boundary wall in the vacant land and vertical extension of exist old wall near vacant land in the complex of kalyanpur Rental housing estate in the district of Burdwan

sl no	Description of item	unit	Qty	Rate	Amount
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil (including mixed soil but excluding laterite or sandstone) including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm.	% m3	25.16	12047.00	3031.00
2	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) (B) Do - by fine sand	%m3	2.288	56872.00	1301.00
3	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	m2	30.50	340.00	10370.00
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof)				
	(a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	m2	0.10	351.00	35.00
	(f) 25 mm to 30 mm shuttering without staging in foundation	m2	0.57	221.00	126.00

5	(I) Cement concrete with graded stone ballast (40 mm size excluding shuttering) In ground floor (A) [Pakur Variety] (a) 1:3:6 proportion	m3	2.2880	5363.00	12270.00
6	Brick work with 1st class bricks in cement mortar (1:6) (a) In foundation and plinth	m3	14.2970	5155.00	73701.0
	(b) In superstructure, ground floor	m3	4.1500	5380.00	22327.0
7	40 mm. thick damp proof course with cement concrete (1:1.5:3) (with graded stone chips 20 mm nominal size) with water proofing compound of approved brand @ 0.2% weight of cement including cost of materials over two coats of non toxic acrylic polymer modified cementitious waterproofing slurry coat complete [cost of water proofing compound and non toxic paint to be paid seperately) for underground water retaining structures. [water proofing as per item no 60 and non toxic paint as per item NO 59 (b) of Section 'C']	m2	15.25	321.00	4895.00

8	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation, basement and upto roof of ground floor / upto 4m (i) Tor steel/Mild Steel	M.T	0.007	68359.00	479.00
9	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	m3	0.071	6293.80	447.00
10	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	m2	90.96	714.00	64945.00
11	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster	m2	287.44	144.00	41391.00
12	Neat cement punning about 1.5 mm. thick in wall, dado, window, sills, floor, drain etc. NOTE : Cement 0.152 cu.m. per 100 sq.m.	m2	25.99	38.00	988.00
13	Earth work in filling in foundation trenches or plinth with good earth, in layers not exceeding 150 mm. including watering and ramming etc. layer by layer complete. (Payment to be made on the basis of measurement of finished quantity of work)				
	(a) With earth obtained from excavation of foundation.	%m3	6.2870	7831.00	492.00

14	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor. (ii) Grill weighing above 16 Kg./sq.mtr and above	Qntl	0.3750	8857.00	3321.00
15	Applying decorative cement based paint of approved quality after preparing the surface including scraping the same thoroughly (plastered or concrete surface) as per manufacturer's specification. In Ground floor: (iii) Two coats.	m2	261.44	53.00	13856.00
16	(b) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.	m2	1.5	31.00	47.00
17	(A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	m2	1.5	86.00	129.00
				TOTAL	**254151.0**

(two lakh fifty four thousand one hundred fifty one only)

27/01/15

Assistant Engineer

Housing Construction Sub-Div-Xiv

Asansol